



DISCONNECT AND REMOVE <E> LAMP AND BALLAST FOR REPLACEMENT OF 120V 5000K LED LAMP WITH 120V DRIVER (ROOLITE FBGL OR EQUAL). CONTRACTOR SHALL PERFORM OPERATIONAL TEST TO ENSURE PROPER FUNCTION OF LIGHTING FIXTURE AND CONTROL.

DISCONNECT AND REMOVE <E> LAMP AND BALLAST FOR REPLACEMENT OF LED LAMP OF MIN. AND DRIVER VIA <E> 277V CIRCUIT AND CONTROL. CONTRACTOR SHALL VERIFY <E> FIXTURE VOLTAGE PRIOR TO ORDERING OF RETROFIT KIT. TOTAL OF 112. COOLING: 14-112W-5K-277V/480V-15 LITH AS2 OR CONTRACTOR SHALL PERFORM OPERATIONAL TEST TO ENSURE PROPER FUNCTION OF LIGHTING FIXTURE AND CONTROL.

LUMINAIRE SCHEDULE							
Symbol	Label	Qty	Catalog Number	Description	Lamp	File	Lumens LLF Watts
●	A	68	Single Arm pole		GLC-LD02	112W_IESNA2 002.IES	11138 0.90 125.9
●	B	20	Double Arm pole		GLC-LD02	112W_IESNA2 002.IES	11138 0.90 251.8

STATISTICS						
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
Site plan	+	0.9 fc	7.1 fc	0.0 fc	N/A	N/A